

- ALL DUCTWORK IS REQUIRED TO BE INSTALLED WITH THE MAXIMUM SUPPORT SPACING LISTED BELOW.
- FOR A COMPLETE LIST OF APPROVED SUPPORT METHODS, SEE THE ENTIRE INSTALLATION AND OPERATION MANUAL.
- DUCTWORK SHALL SLOPE NOT LESS THAN 1/16" PER LINEAR FOOT TOWARDS THE HOOD OR AN APPROVED GREASE COLLECTION RESERVOIR.
- WHERE HORIZONTAL DUCTS EXCEED 75 FEET IN LENGTH, THE SLOPE SHALL NOT BE LESS THAN 3/16" PER LINEAR FOOT.

VERTICAL			
TYPE	WALL SUPPORT (FT)	CURB SUPPORT (FT)	FLOOR SUPPORT (FT)
2R & 2R HT (5'-16')	20'	24'	24'
2R (18')	18'	24'	24'
3R & 3Z (5'-24')	10'	24'	24'
3Z (26' - 36')	10'	20'	20'

DO NOT LEAK TEST USING SMOKE BOMBS CONTAINING
CHLORINES/CHLORIDES. CONSULT WITH CAPTIVEAIRE
FOR PROPER LEAK TESTING METHODS.

RAVE
Southern California Office
www.captiveaire.com



All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

[illegible]

DRAWN BY: SDT

PANDA PROJECT #: - S8-22-D8690
C&P PROJECT #: - 2210806



03.04.2022



TRUE WARM AND WELCOME 2200
3030 DERITA ROAD
CONCORD, NC 28027

M-410

HOOD DETAIL PLAN

TRUE WARM & WELCOME 2200 R4